

## State Line to Highland Junction

## Munster & Highland, IN Lake County

### **Project Team:**

- Project Manager: Peter Faberbock
- Consulting Engineer: EN Engineering
- General Contractor: NPL

### **Project Scope:**

- Install approximately 3.4 miles of 24-inch high pressure pipeline (API 5L x65, 0.375" wall 720 PSIG design and 600 PSIG MOP)
- Install Filter and Launcher at Stateline Station, and tie-in to existing line
- Relocate and upgrade an existing regulator station at Fisher Street to provide distribution service to Community Hospital and the Town of Munster
- Upgrade the current tie-in at the Highland Junction connection point
- Abandon approximately 3.4 miles of 22-inch high pressure pipeline
- Temporary road closures and bike path closure

### **Construction Schedule**

- Project Start Date: April 1, 2016
- Project completion date: September 30, 2016
- RESTRICTIONS
  - Work on Calumet, Columbia, and Fischer Street shall be done when school is out. May 25<sup>th</sup> to August 12<sup>th</sup>

### **Communication Plan**

- Direct Mailer and Fact Sheet
- Press Release to local media
- Town Newsletter/Water Bill – NIXEL Program
- Munster School Corp Robo Call
- Placement of Signs

# 24" STATE LINE TO HIGHLAND JUNCTION GAS MAIN REPLACEMENT PROJECT



LEGEND	
	HORIZONTAL DIRECTIONAL DRILL
	OPEN CUT









