

DOCUMENT 01 26 63

CHANGE ORDER

NUMBER: 1

PROJECT: Paving and Traffic Calming Improvements CCMG 24-1 – Meadow, Highland, Linden and Independence

DATE OF ISSUANCE: 9/9/2024 EFFECTIVE DATE: 9/9/2024

OWNER: Town of Munster

OWNER'S Contract No. MUNST 178099

CONTRACTOR: Milestone Contractors

ENGINEER: SEH of Indiana

You are directed to make the following changes in the Contract Documents.

Description: Watermain Service Changes
EXCAVATION COMMON – REMOVE 1340.00 CYS
NO. 2 STONE – REMOVE 396.00 TONS
GEOGRID, TYPE 1B – REMOVE 8781.00 SYS
GEOTEXTILE – REMOVE 8781.00 SYS
COMPACTED AGGREGATE BASE, NO. 53 – REMOVE 2900.00 TON
MILLING ASPHALT, 4 IN. – REMOVE 7990.00 SYS

HMA SURFACE TYPE B, 12.5 mm – ADD 970.00 TONS
MILLING ASPHALT, 2 IN. – ADD 7990.00 SYS
CRACKS IN PCCP, FILLED – ADD 100.00 LFT
SAWCUT MONOLITHIC CURB & GUTTER – ADD 1765.00 LFT

Reason for Change Order:

The existing pavement on Meadow Lane and Highland Place is 2IN of HMA surface on concrete pavement (PCCP). The existing PCCP is in good condition and does not need to be removed. Meadow Lane and Highland Place will be repaved by milling the existing 2IN of HMA, scarifying the existing PCCP surface, patching any cracks in the PCCP, sweeping the PCCP and removing any debris, placing tack coat, and replacing 2IN of HMA surface.

The existing curb and gutter on Meadow Lane and Highland Place is monolithic and needs to be sawcut at the pavement face to be removed.

Attachments: (List documents supporting change)

Milestone Request for Additional Pricing – Munster CCMG 24-1 Highland and Meadow Pavement Removal

CHANGE IN CONTRACT PRICE:	CHANGE IN CONTRACT TIMES:
Original Contract Price	Original Contract Times
\$ 1,099,982.10	Substantial Completion: _____
	Ready for final payment: _____
	days or dates
Net changes from previous Change Orders No. ____ to No. ____	Net changes from previous Change Orders No. ____ to No. ____
\$ 0.00	_____
	(days)
Contract Price prior to this Change Order	Contract Times prior to this Change Order
\$ 1,099,982.10	Substantial Completion: _____
	Ready for final payment: _____
	days or dates
Net Increase (Decrease) of this Change Order	Net Increase (Decrease) of this Change Order
\$ (87,643.30)	_____
	(days)
Contract Price with all approved Change Orders	Contract Times with all approved Change Orders
\$ 1,012,338.80	Substantial Completion: _____
	Ready for final payment: _____
	days or dates

RECOMMENDED:

By: Kim Wenzel
Engineer (Authorized Signature)

Date: 9/9/2024

APPROVED:

Town of Munster

By: _____
Town Manager

Date: _____

ACCEPTED:

By: Carla A. [Signature]
Contractor (Authorized Signature)

Date: Sept 10, 2024

END OF SECTION