
# SITE DEVELOPMENT PLANS FOR: Self Storage Facility

45th Ave & Fran-Lin Pkwy Munster, IN 46321



# LOCATION MAP



# SITE CONTACTS

#### AGENCY: Town of Munster Public Works Munster, IN 46321 Munster, IN 46321 PHONE: 219-836-6900 PHONE: 219-836-6990 CONTACT: CONTACT: Sergio Mendoza EMAIL: EMAIL: smendoza@munster.org AGENCY: Town of Munster Public Works AGENCY: Town of Munster Community Development ADDRESS: 1005 Ridge Rd ADDRESS: 1005 Ridge Rd Munster, IN 46321 Munster, IN 46321 PHONE: 219-836-6900 PHONE: 219-836-6990 CONTACT: CONTACT: Sergio Mendoza EMAIL: EMAIL: smendoza@munster.org **TRANSPORTATION** FIRE DISTRICT AGENCY: Town of Munster Public Works AGENCY: Town of Munster Fire Department ADDRESS: 1005 Ridge Rd ADDRESS: 550 Fisher St Munster, IN 46321 Munster, IN 46321 PHONE: 219-836-6900 PHONE: 219-836-6960 CONTACT: CONTACT: Mark Haiduk EMAIL: EMAIL: mhajduk@munster.org STORMWATER AGENCY: Town of Munster Public Works ADDRESS: 1005 Ridge Rd Munster, IN 46321

# SHEET INDEX

DESCRIPTION	DWG. NO			
CIVIL TITLE SHEET	C001			
EXISTING CONDITIONS & DEMOLITION PLAN	C002			
SITE PLAN	C101			
GRADING & DRAINAGE PLAN	C201			
SPOT ELEVATIONS PLAN	C202			
DETENTION POND DETAILS	C203			
EROSION CONTROL PLAN - PHASE 1	 C211			
EROSION CONTROL PLAN - PHASE 2	C212			
EROSION CONTROL PLAN - PHASE 3	C213			
SEDIMENT BASIN DETAILS	 C214			
UTILITY PLAN	C301			
STORM DRAINAGE PROFILES	C401-C402			
SITEWORK NOTES AND DETAILS	C501-C507			
LANDSCAPE PLAN	LS-1 - I S-2			

# **DEVELOPER**

CONTACT: Gordo Kolb

COMPANY: GHK Developments, Inc. ADDRESS: 3920 Magazine St. New Orleans, LA 70115 PHONE: 504-866-7300 EMAIL: EMAIL: gordo@ghkinc.com

# CIVIL ENGINEER

COMPANY: | Bluewater Civil Design, PLLC ADDRESS: 718 Lowndes Hill Rd Greenville, SC 29607 PHONE: 864-326-4204 CONTACT: Jason S. Henderson, P.E. EMAIL: jason@bluewatercivil.com

# **SURVEYOR**

LAND DISTURBANCE - EROSION CONTROL

PHONE: 219-836-6900

ADDRESS: 1005 Ridge Rd

PHONE: 219-836-6900

AGENCY: Town of Munster Public Works

Munster, IN 46321

CONTACT: EMAIL:

CONTACT: EMAIL:

> COMPANY: | Torrenga Surveying, LLC ADDRESS: 907 Ridge Rd Munster, IN 46321 PHONE: 219-836-8918 CONTACT: J. Stuart Allen EMAIL: stuart.allen@torrenga.com

# **ARCHITECT**

Jared Ducote, Architect COMPANY: 125 W Romana Street, Suite 660 Pensacola, FL 32502 PHONE: 850-439-1552 CONTACT: Jared Ducote, AIA EMAIL: jared@ducotedesign.com

I hereby certify that these plans (except for Architectural, Landscape) were prepared by me or under my direct supervision and that I am a duly Registered Professional Engineer under the laws of the State of Indiana and that I ent to prepare this document. 09/16/2025

ARISTOPHER L. PRICE - IN P.E. # 12100391


SC C04212 - GA PEF005865 NC P0868 - AL CA4065E



Self

REVISION	DATE	COMMENT
Α	8-7-2025	ISSUED FOR REVIE
В	9-16-2025	ISSUED FOR PERMI

CIVIL TITLE SHEET



Project Number: 2025-104


DWG Name: 2025-104 D1.dwg Drawing Scale: as noted Date of Project: 8-1-2025 \_ Christopher L. Price, P.E.

Certificates of Authorization: SC C04212 - GA PEF005865 NC P0868 - AL CA4065E

torage Self

STATE OF

**EXISTING** CONDITIONS & **DEMOLITION PLAN** 




Drawing Scale: as noted Date of Project: 8-1-2025 Christopher L. Price, P.E.

Certificates of Authorization SC C04212 - GA PEF005865

NC P0868 - AL CA4065E

STATE OF


CIVIL SITE PLAN





Project Number: 2025-104 DWG Name: 2025-104 D1.dwg


Drawing Scale: as noted

STATE OF









Project Number: 2025-104


Drawing Scale: as noted Date of Project: 8-1-2025


Christopher L. Price, P.E.
South Carolina PE# 22396
Indiana PE # 12100391


Certificates of Authorization SC C04212 - GA PEF005865

STATE OF

**EROSION CONTROL** 








#### DRY SEDIMENT BASIN - GENERAL NOTES


Sediment basins should not be placed in waters of the state or USGS blue-line streams (unless approved by Federal Authorities).

- Sediment basin's side slopes shall be seeded and, when necessary, stabilized with vegetative or synthetic matting to prevent the formation of rills and
- Install three (3) rows of porous baffles with a minimum spacing of 10 feet. Baffles should ultimately be placed to maximize the space between each row of baffles and the basin's inlets/outlets. Only two (2) rows of baffles are necessary for basins that are less than 50 feet in length.
- Porous Baffles should be composed of coir-based materials or TRMs with a light penetration (open spaces) between 10-35%. These materials should not have loose straw. Silt Fence may not be used as Porous Baffles.
- Each porous baffles shall be installed across the entire width of the basin and along the basin's side slope until the height of the baffle intersects the slope. Install skimmer and coupling (as necessary) to riser structure at orifice along
- bottom of the principle spillway's riser structure. (refer to skimmer manufacturer for installation procedures and skimmer specifications.) Skimmer should be equipped with a mechanism, such a s a rope, to allow easy access to skimmer to unclogged orifice or perform other necessary
- maintenance. Stormwater runoff entering the basin must be directed into proper BMPs to
- prevent erosion along side slopes and to prevent scour at the basin's inlets. The forebay berm should consist of riprap, gabion, or an earthen berm with a rock filled outlet that is constructed across the bottom of the basin's width. 10. An additional cleanout stake for the forebay area is recommended and should
- be marked for cleanout at 50% of provided sediment storage. 1. The elevation of the emergency spillway should be at least 1 foot below the top of the embankment. The emergency spillway should not be located on fill material, when possible. Riprap and geotextile liner should be placed on all spillways that must be located on fill material.

#### DRY SEDIMENT BASIN - INSPECTION AND MAINTENANCE

- The key to a functional sediment basin is weekly inspections, routine
- maintenance, and regular sediment removal. Attention to sediment accumulations within the basin is extremely important. Accumulated sediment deposition should be continually checked and removed when necessary.
- Remove accumulated sediment when it reaches 50% of the design sediment
- storage volume or  $\frac{1}{2}$  the height of the riser structure, whichever is reached first. Removed sediment from the basin shall be placed in stockpile storage areas or spread thinly across the disturbed area. Stabilize the removed sediment after it is relocated.
- Inspections of sediment basins should be conducted once every calendar week and, as recommended, within 24- hours of each rainfall event that produces 1/2-inch or more of precipitation.
- All temporary sediment basins, which are not to be converted to a detention basin post-construction, should be removed within 30 days after final site stabilization is achieved.
- Disturbed areas resulting from the removal of the sediment basin should be permanently stabilized and additional BMPs, such as silt fence, should be utilized to accept stormwater runoff from this disturbed area until final stabilization is reached.






Drawing Scale: as noted


Date of Project: 8-1-2025 Engineer of Record: Christopher L. Price, P.E. South Carolina PE# 22396 Indiana PE # 12100391

Certificates of Authorization: SC C04212 - GA PEF005865


NC P0868 - AL CA4065E

SEDIMENT BASIN **DETAILS** 





SD Profile A Horizontal Scale: 1" = 20' Vertical Scale: 1" = 5'



Horizontal Scale: 1" = 20' Vertical Scale: 1" = 5'


Christopher L. Price, P.E.
South Carolina PE# 22396
Indiana PE # 12100391

SC C04212 - GA PEF005865 NC P0868 - AL CA4065E


torage Munster IN Self



STORM DRAINAGE PROFILES



SD Profile C Horizontal Scale: 1" = 20' Vertical Scale: 1" = 5'



SD Profile C4
Horizontal Scale: 1" = 20'
Vertical Scale: 1" = 5'

torage Munster IN

Certificates of Authorization: SC C04212 - GA PEF005865 NC P0868 - AL CA4065E

O9/16/2025

NO. 12100391

STATE OF

WOIANA

WO

PLAN EVISION	ISSUE DATE	ISSUE COMMENT
Α	8-7-2025	ISSUED FOR REVIEW
В	9-16-2025	ISSUED FOR PERMIT

STORM DRAINAGE PROFILES

C402

1. The Contractor shall call 811 Utility Locate Service prior to start of any construction activity.

instructions once approved to do so by the Owner's Representative or as required by law.

- 2.1. Survey Information provided by Torrenga Surveying (219-836-8918). The Contractor shall verify all benchmarks, easements, the location and invert elevation of all underground utilities within the construction area, verify property corners, and verify topography before any construction is begun.
- 2.2. The Contractor shall contact all utility companies prior to excavation to request a locate for all buried cables and underground utilities in the construction area or utilities that will be impacted by construction.
- 3.1. The Contractor shall have copies of any necessary encroachment and construction permits prior to entering any right-of-way or beginning construction.
- 3.2. Permits typically required include but are not limited to: State NPDES Coverage, Local Issuing Authority Grading Permit, DOT Encroachment Permits (access and utility taps), State or Local Water Authority water extension permit, State or Local Sewer Authority sewer extension permit, Fire Marshall approval, and Local Municipality Zoning and Site Plan Approval.
- 3.3. The Contractor shall immediately notify the Owner's Representative when notices or verbal instructions are received from regulatory authorities, inspectors, or similar. The Contractor shall proceed with work associated with such notices or
- 4.1. By Law, the Contractor shall comply with all OSHA regulations, including safety protocol, safety gear, safety education,
- 4.2. The Contractor is exclusively responsible for the conditions of the site, including safety of all persons and property
- throughout the term of the project construction, 24 hrs per day/ 7 days per week. 4.3. The Engineer's review of the Contractor's work product and performance will not include review of the Contractors safety
- programs. Such reviews are to be by OSHA inspectors and the Owner's Representative. 4.4. The Contractor is responsible for providing and maintaining all necessary traffic control devices during construction. Under no circumstances shall equipment be loaded or off-loaded on an open roadway. If such activity is required the Contractor shall coordinate shutting down the road with the appropriate DOT and utililize appropriate traffic control warning devices.
- 5.1. The Contractor is responsible for reviewing the requirements in the SWPPP drawings and maintaining all records as required by Local, State, and Federal Laws.
- 5.2. The SWPPP manual/plans shall be kept on-site in a secure location accessible to the inspector at all times during construction
- 5.3. The Contractor shall post a 24-Hour Contact and phone # and rain gauge at the job site.
- 6. Pre-construction Meeting: 6.1. The Contractor shall immediately contact the state or local issuing authority, utility companies, etc. and set up a pre-construction conference at the site.
- 6.2. The Contractor shall make sure the Engineer of Record, Owner, Inspector, Superintendent, and any relevant erosion control sub-contractor are in attendance.
- 6.3. The Contractor shall develop an attendance sign in sheet and keep minutes of the meeting with the SWPPP. 7.1. The Contractor shall protect trees that are noted to remain on the plans or as marked in the field by Owner's
- Representative. Trees that are to be protected shall have a protective fencing installed around the critical root zone (1' for every 1" DBH) and shall not disturb the root zone of such trees unless approved to do so in writing by the Owner's
- 7.2. The Contractor shall remove all trees and vegetation that interfere with new construction not noted to be protected. Remove debris from site or burn in accordance with local laws.
- 7.3. The Contractor shall be responsible for obtaining all necessary dumping or burning permits. 8. Earthwork:
- 8.1. The Contractor shall grade the site to the lines and grades shown and shall proof-roll and test compaction on all areas. 8.2. The Contractor shall retain the services of a testing company to test all areas to insure they meet the minimum
- compaction requirements as noted in these notes or as required by the Owner's Geotechnical Engineer's report. 8.3. The Grading Contractor shall proof-roll the construction area. All soft spots shall be undercut and re-compacted with suitable structural fill material and re-tested. Proof-rolling shall be observed by a qualified Geotechnical Engineer or
- 8.4. All proposed elevations shown are finish grade elevation and the Grading Contractor shall deduct quantities from the finished grades as required due to depth of pavement sections, sidewalks, turf areas with topsoil, building foundations, etc. to develop the true finished sub-grade.
- 8.5. Any topsoil in the construction area shall be stripped to a depth as required (see Geotechnical Report for referenced depths) and stockpiled as directed by the Owner's Representative. Topsoil shall be re-used on-site unless approved otherwise.
- 8.6. The contractor shall reference the Geotechnical Report for compaction requirements. 8.7. All excavation shall be "Classified Excavation". Excavation shall be "Classified" as "Common Excavation" or "Rock Excavation". Rock Excavation is removing material that has been observed by the testing company to only be removed by
- blasting or with an air hammer. Common Excavation is removing of materials by means of ripping and do not fall in the category of rock excavation as defined above (includes boulders, typical weathered rock, etc.) 8.8. The classification of soils include: topsoil, fill material, unsuitable material, and rock excavation. The classification of soils is the responsibility of the geotechnical soil testing firm.
- 8.9. Rock Excavation is classified as: 8.9.A. Massive rock excavation - Material of 1 c.y. or more unable to be excavated with a single tooth ripper drawn by a crawler tractor having a minimum draw bar rated at not less than 53,000 pounds (Caterpillar D-8 or equivalent).
- 8.9.B. Trench excavation Material of  $\frac{1}{2}$  c.y. or more which cannot be excavated with a power shovel having the capacity of at least that of a Caterpillar 225. 8.10. Fill material (including off site borrow) shall be from a source approved by the soil testing company and shall be free of
- roots, organics and boulders larger than 1 cubic foot. Fill shall be placed in 8" lifts and compacted as specified. The fill shall meet the specifications as required by the testing company or as indicated in the Geotechnical Report. 8.11. All existing pavement to be left in a fill area shall be scarified prior to placement of any fill material.
- 8.12. All slopes steeper than 4:1 receiving fill shall be plowed and scarified to enhance the bonding of new fill with existing
- 8.13. The Grading Contractor shall include in contract price the total cost and unit price for all cut/fill necessary for earthwork balance including if necessary unit prices for hauling in material and hauling off material.
- 8.14. The wetting/drying of soils to achieve specified compaction shall be included in the Grading Contractor's contract price. 8.15. All private roads and parking lots shall have a minimum 5'-0" wide grassed shoulder with a maximum 2.0% cross slope. All
- public roads shall have a 6'-0" wide grassed shoulder with a maximum 2.0% cross slope. 8.16. Tolerances for final constructed grades shall be plus or minus 0.05 feet. The final graded surface under all building slabs shall be within a tolerance of 3/8" when measured with a 10' straight edge. All designated ADA accessible paths shall have a maximum 2.00% (1:50) cross-slope and maximum 5.00% (1:20) running slope, no exceptions. All designated ADA accessible parking spaces and landings (including 4' area out from all doorways) shall have a maximum 2.00% (1:50) slope in any direction,
- no exceptions. All designated ADA accessible ramps shall have a maximum slope of 8.33% (1:12), no exceptions. 9.1. Reinforced Concrete Pipe (RCP) shall conform to ASTM C 76, latest edition. RCP with cover less than 15' and greater than 2' shall be CLASS III bell and spigot type and installed with flexible plastic (Bitumen) gaskets at all joints, unless otherwise noted. All other depths of cover shall be CLASS IV or V as noted. Gaskets shall comply with AASHTO M-198 751, Type B, and
- shall be installed in strict accordance with pipe manufacturer's recommendations. 9.2. All corrugated plastic pipe shall meet the requirements of AASHTO M-294, Type S, shall be smooth interior with annular corrugated exterior. HI-Q Sure-Lock 10.8 pipe, ADS, N-12, or approved equal. All joints shall be bell and spigot and shall meet the requirements of AASHTO M-294, shall be watertight, meeting the requirements of ASTM D 3212. The gaskets shall be made of Polyisoprene meeting the requirements of ASTM F 477. Installation shall conform to AASHTO M-294, ASTM D-2321, and manufacturers installation procedures. The maximum cover allowed over the top of CCP is 15'.
- 10.1. All water shall be per the approved drawing and the latest standards and specifications of the local water authority. The Contractor shall coordinate construction with the local water authority, including schedule & laydown areas. Any deviation from the approved plan shall be brought to the attention of the Engineer of Record and the appropriate inspector immediately.
- Deviations from the approved plan shall not be installed unless approved in writing by the local water authority. 10.2. Sanitary sewer lines and appurtenances shall be installed per the approved drawing and latest standards and specs of the local sewer authority 10.3. The Contractor shall insure they have the proper approvals from the <u>Town of Munster</u>, prior to installation of any domestic
- water, fire water, or sanitary sewer system. 10.4. All utility trenches shall be thoroughly compacted as required by the local authority and tested to prevent settlement and
- damage to future pavement and structures. 10.5. The Contractor shall be responsible for relocating any existing utilities necessary for site construction, including all
- permits and fees. The Contractor is responsible for contacting all utility companies and including in his price all fees, charges, expenses, etc. in his cost to the Owner. 11. Pavement
- 11.1. All paving work (materials and construction) shall comply with <u>INDOT</u> standards and specifications for Hot-mixed Asphalt Pavement. (See Pavement Section Details for depths of layers).
- 11.2. All pavement shall be installed on a finished and well-drained sub-grade compacted as specified in previous notes. 11.3. Base course material for asphalt pavement shall be stone aggregate base course (ABC) and compacted to 100% modifed
- 11.4. Concrete pavement shall consist of a base course with stone aggregate base course compacted to 100% modified proctor. The concrete shall be poured with WWF. Concrete shall be broom finished and jointed as required.
- 11.5 Concrete curb and gutter ON-SITE AND OUTSIDE OF INDOT RIGHT OF WAY shall be per ON-SITE 18" Curb and Gutter. 11.6. Concrete curb and gutter <u>WITHIN INDOT RIGHT OF WAY</u> shall be <u>INDOT STANDARD 30"</u> wide with standard curb constructed with 4,000 PSI concrete with expansion joints and contraction joints installed to comply with state DOT standard
- specification for materials and construction of curb and gutter 11.7. All parking lot striping shall be per State D.O.T. specifications with two (2) coats of paint applied. The bases of all light poles, all bollards, and the face of all sidewalk, are to be painted TRAFFIC YELLOW. The Contractor is responsible for providing fire lane striping and signage meeting all local requirements. Parking lot striping shall be reflective paint (see site plan for color). Stop bars, directional arrows, and parcel pickup are to be reflective paint (see site plan for color). All ADA striping
- shall be reflective ADA blue. 12. Erosion Control and Drainage: 12.1. All areas outside paving limits and building foundations shall have a minimum 4" layer of topsoil added and permanently

12.3. The sequence of work shall conform to the erosion control narrative.

- grassed in accordance with state seeding specifications or landscaped per the Landscape Plan if applicable. 12.2. The Grading Contractor shall maintain positive drainage away from buildings at all times. The Contractor shall bring to the attention of the Engineer any areas that may not drain properly during construction.
- 12.4. Sediment controls during construction shall comply with all local, state, and federal laws and regulations. After all sitework is completed and grassing established, the Grading Contractor shall remove all silt from the site and legally dispose of all silt off-site at no additional cost to the Owner, or bury on-site in non-structural area.
- 12.5. No work shall begin on site until approval from the <u>TOWN OF MUNSTER</u> and an <u>IDEM NPDES</u> permit has been issued, and a pre-construction meeting has been completed with the <u>TOWN OF MUNSTER</u>, the Owner, and the Engineer.
- 13.1. The Contractor shall review the plans and specifications carefully and shall immediately notify the Engineer for a review if any discrepancies are discovered at the site or on the drawings.
- 13.2. All reference to state standards and specifications are made from the <u>Indiana Department of Transportation Standard</u> Specifications for Roads and Bridges, latest edition and Roadway Standard Drawings, latest edition.
- 13.3. All dimensions shown on the drawings are measured as shown and from outside face of building wall or to face of curb line, unless otherwise noted. Curb and Gutter is shown as three (3) lines (outside edge of gutter, face of curb, and back of curb).
- 13.4. All retaining wall design shall be per Architectural Plan or separate Structural Engineer's design notes and details. The Civil
- Plans shall not be considered plans for retaining wall construction.
- 13.5. The General Contractor is responsible for posting all required bonds that General Contractors are allowed to post. 13.6. If any conflicts between the notes, details, specifications, and drawings occur then by rule the stricter shall govern.

#### STANDARD EROSION AND SEDIMENT CONTROL NOTES

- 1. Sediment and erosion control devices shall be installed and functioning prior to beginning any project
- 2. Soil stabilization shall be achieved on any area of a site where land-disturbing activities have temporarily or permanently ceased according to the following schedule:
- All perimeter dikes, swales, ditches, perimeter slopes and all slopes steeper than 3 horizontal to 1 vertical (3:1) shall be provided temporary or permanent stabilization with ground cover as soon as practicable but in any event within 7 calendar days from the last land-disturbing activity.
- All other disturbed areas shall be provided temporary or permanent stabilization with ground cover as soon as practicable but in any event within 14 calendar days from the last land-disturbing
- 3. To secure the project site, locate limits of construction, protect areas that are to remain undisturbed, and prevent migration of construction debris, orange construction fencing shall be installed around areas not requiring silt fencing. Any accumulation of construction debris on public roadways or adjacent properties shall be removed within 24 hours. Care shall be taken when installing construction fencing to not obscure oncoming traffic at intersections, adjacent driveways and the project construction entrance.

#### Inspections and Maintenance

- 4. All sediment and erosion control devices shall be inspected every seven (7) days minimum or after every rain event. Damaged or ineffective devices shall be repaired or replaced, as necessary.
- 5. All sediment and erosion controls shall be inspected, at the specified inspection frequency, until construction is complete and the site is permanently stabilized.
- 6. All erosion control devices shall be properly maintained during all phases of construction until the completion of all construction activities and all disturbed areas have been permanently stabilized. Additional control devices may be required during construction in order to control erosion and/or offsite sedimentation. All temporary control devices shall be removed once construction is complete and the site is permanently stabilized.
- 7. All existing and new storm water structures, affected by this project, shall be inspected and maintained clean of accumulated demolition debris or sediments. The inspection and maintenance of these structures shall be accomplished on the same schedule as the sediment and erosion control devices.
- Disposal of all recovered sediments and construction debris shall be in accordance with all applicable City, State and Federal Regulations.
- 9. All erosion and sediment control plans and documentation (e.g., certification statements, inspection records, and maintenance records) shall be available on site during construction. All plans and documents shall be updated as required per NPDES General Permit.

#### Best Management Practices (BMPs)

- 10. A stabilized construction entrance shall be installed and maintained on the project site. Storm water inlet protection shall be provided for all inlets (upstream and downstream) within 50 ft. of the construction entrance (on both sides of the public roadway).
- 11. During the course of construction activities erosion and sediment controls shall be used to prevent; sediment accumulation on public roadways (including street gutters), sediment laden runoff from entering into existing storm water system inlets or depositing on adjacent properties, and airborne dust migration off-site. Any accumulation of sediment from the project site on public roadways or adjacent properties shall be removed within 24 hours.
- The contractor must take necessary action to minimize the tracking of mud onto the paved roadway construction areas. The contractor shall daily remove mud/soil from pavement, as may be required.
- 12. Provide silt fence and/or other control devices, as may be required, to control soil erosion during utility construction. All disturbed areas shall be cleaned, graded, and stabilized immediately after the utility installation.
- 13. Silt fencing shall be placed no closer than 5 ft. downhill from the toe of any fill area.
- 14. Temporary stockpiling of useable or waste materials for more than fourteen (14) days shall have appropriate erosion and sediment control measures installed. Temporary stockpiles shall be placed away from storm water inlet structures, adjacent property and public roadways.
- 15. Litter, construction debris, oils, fuels, building products with significant potential for impact (such as stockpiles of freshly treated lumber), and construction chemicals that could be exposed to storm water must be prevented from becoming a pollutant source in storm water discharges.
- 16. Temporary diversion berms and/or ditches will be provided as needed during construction to protect areas from upslope runoff and/or to divert sediment laden water to appropriate traps or stable outlets.
- 17. If necessary, slopes which exceed eight (8) vertical feet should be stabilized with synthetic or vegetative mats, in addition to hydro seeding. It may be necessary to install temporary slope drains during construction. Temporary berms may be needed until the slope is brought to grade.
- 18. Cat track or surface roughening is required for all slopes greater than 4:1 prior to seeding and lying of synthetic or vegetative mats. Cat tracking or surface roughening shall produce a surface with furrows running cross slope, parallel with slope contours, and perpendicular to surface runoff.

#### Close-out

- 19. The site shall be considered permanently stabilized when all surface disturbing activities are complete and either of the two following criteria are met:
- a. A uniform (e.g., evenly disturbed, without large bare areas) perennial vegetative cover with a density of 70% of the native background vegetative cover for the area has been established on all unpaved areas and areas not covered by permanent structures, or
- b. Equivalent permanent stabilization measures (such as riprap, gabions, or geotextiles) have been
- 22. Upon completion of construction activities and meeting the conditions of permanent stabilization a Notice of Termination (NOT) shall be submitted to IDEM and a copy of the submitted NOT shall be sent to the Town of Munster.

## IDEM SURFACE STABILIZATION

#### **MATERIALS**

- Soil Amendments Select materials and rates as determined by a soil test (contact your county soil and water conservation district or cooperative extension office for assistance and soil information, including available soil testing services) or 400 to 600 pounds of 12-12-12 analysis fertilizer, or equivalent. Consider the use of reduced phosphorus application where soil tests indicate adequate phosphorous levels in the soil profile.
- Seed Select appropriate plant species seed or seed mixtures on the basis of quick germination, growth, and time of year to be seeded (see Table 1). Mulch
- •• Straw, hay, wood fiber, etc. (to protect seedbed, retain moisture, and encourage plant
- •• Anchored to prevent removal by wind or water or covered with manufactureed erosion control

#### Table 1. Temporary Seeding Specifications

Seed Species <sup>1</sup>	Rate per Acre	Planting Depth	Optimum Dates <sup>2</sup>		
Wheat or Rye	150 lbs.	1 to 1½ inches	Sept. 15 - Oct. 30		
Spring Oats	100 lbs.	1 inch	March 1 – April 15		
Annual Ryegrass	40 lbs.	1/4 inch	March 1 – May 1 Aug. 1 – Sept. 1		
German Millet	40 lbs.	1 to 2 inches	May 1 – June 1		
Sudangrass	35 lbs.	1 to 2 inches	May 1 – July 30		
Buckwheat	60 lbs.	1 to 2 inches	April 15 – June 1		
Corn (broadcast)	300 lbs.	1 to 2 inches	May 11 – Aug. 10		
Sorghum	35 lbs.	1 to 2 inches	May 1 – July 15		

Perennial species may be used as a temporary cover, especially if the area to be seeded will remain idle for more than one year (see Permanent Seeding on page

<sup>2</sup>Seeding done outside the optimum seeding dates increases the chances of seeding failure. Dates may be extended or shortened based on the location of the project site within the state.

Mulch alone is an acceptable temporary cover and may be used in lieu of temporary seeding, provided that it is appropriately anchored. A high potential for fertilizer, seed, and mulch to wash exists on steep banks, cuts, and in channels and areas of concentrated flow.

#### **APPLICATION**

#### **Seedbed Preparation**

- Test soil to determine pH and nutrient levels. Apply soil amendments as recommended by the soil test. If testing is not done, apply 400 to 600
- pounds per acre of 12-12-12 analysis fertilizer, or equivalent. 3. Work the soil amendments into the upper two to four inches of the soil with a disk or rake
- operated across the slope.

Select a seed species or an appropriate seed mixture and application rate from Table 1.

the depth shown in Table 1.

Apply seed uniformly with a drill or cultipacker seeder or by broadcasting. Plant or cover seed to

- 1.1. If drilling or broadcasting the seed, ensure good seed-to-soil contact by firming the seedbed with a
- roller or cultipacker after completing seeding operations. 1.2. Daily seeding when the soil is moist is usually most effective.
- 1.3. If seeding is done with a hydroseeder, fertilizer and mulch can be applied with the seed in a slurry
- 2. Apply mulch (see Mulching on page 55 or Compost Mulching on page 59) and anchor it in place.

#### **MAINTENANCE**

- Inspect within 24 hours of each rain event and at least once every seven calendar days.
- Check for erosion or movement of mulch and repair immediately.

acre of nitrogen in February or March.

Monitor for erosion damage and adequate cover (80 percent density); reseed, fertilize, and apply mulch where necessary.

If nitrogen deficiency is apparent, top-dress fall seeded wheat or rye seeding with 50 pounds per

## **EROSION CONTROL NOTES**

#### SITE INFORMATION:

 Existing Condition: UNDEVELOPED LOT

 Proposed Condition: RETAIL USE - PAVEMENT & BUILDING Proposed Work: EXCAVATION & FILLING, BUILDING CONSTRUCTION, PAVING, &

STORM DRAINAGE & UTILITY INSTALLATION

Existing Soils: Rs (Rensselaer Loam), Bn (Bono Silty Clay) INLET PROTECTION, SILT FENCE, ROCK CHECK DAMS, BMPs Shown on Plan:

CONSTRUCTION ENTRANCE, SKIMMER BASIN ±3.7 - ACRES Disturbed Area:

## EROSION CONTROL SEQUENCE (for Contractor):

#### Phase I - Sheet C211:

- Schedule a Pre-Construction Meeting at the site with the Owner, Engineer, and any local inspectors at least 72 hrs prior to commencement of construction.
- Install the permit box on-site.
- Clearly mark the limits of disturbance.
- Install construction entrance, install BMPs, construct temporary sediment basin and install any perimeter silt fence BMP protection prior to demolition activities. Establish main Construction Entrance/ Exit.
- Continuously maintain all BMPs throughout construction. Remove accumulated sediment
- from BMPs and clean-out Sediment Basins as noted on plans.

#### Note: Contractor's price for work shall be all inclusive for installing and maintaining BMPs as shown on drawings.

permanently stabilized until the controls are removed.

Maintenance of Sediment and Erosion Control Measures must continue until the site is

## Phase II - Sheet C212:

- Install temporary ditches/swales to divert stormwater to sediment basins as shown on sheet C212.
- Begin clearing and grubbing.
- Begin topsoil stripping as noted. Topsoil shall be re-used in grass or parking lot landscape islands/areas and on slopes after rough grading operations.
- Continuously maintain all BMPs thoughout construction. Remove accumulated sediment from BMPs and clean-out sediment trap as noted on plans. NOTE: Contractor's price for work shall be all inclusive for installing and maintaining BMPs as shown drawings.
- Rough grade site. Temporary or Permanent grassing shall be established on areas disturbed with no activity for 7 days. Continuously remove accumulated silt/sediment
- Construct Building Laydown area and and Staging area around the proposed building pad. Install storm drainage, utilities, etc. as grade allows.
- Install Catch Basin Inlet protection at all catch basins as they are constructed.
- Install temporary ditches/swales to divert stormwater to catch basins as shown on sheets
- Install Slope Matting on all slopes 3:1 or steeper (Tensar RECP per detail) on all slopes as noted on the Phase II Erosion Control Plan.

#### Phase III - Sheet C213

- Finalize Fine Grading and construct curb & gutter.
- Place stone as soon as possible on all areas to be paved and building pads.
- Respread topsoil (4" min.) evenly on unimproved areas and areas with no impervious
- surfaces proposed including all slopes. 14. Permanently grass all areas not to be paved or built upon (ie outpads) or that receives landscaping/mulch. Establish 100% coverage with 70% density
- Finalize all paving and grassing to achieve final stabilization. Remove silt/sediment from all BMPs and dispose of legally or on-site as approved by the
- Once site is finalized with 100% grass coverage and 70% density contact local inspector
- and Engineer of Record for closeout inspection.

permanently stabilized until the controls are removed.

- Address any punchlist items from closeout inspection. Remove temporary BMPs once site is accepted for closeout by local issuing authority.
- Contact Engineer and schedule final walkthrough. Engineer will coordinate with Owner to apply for NOT (Stormwater). Note: Contractor's price for work shall be all inclusive for installing and maintaining BMPs as

shown on drawings.

Maintenance of Sediment and Erosion Control Measures must continue until the site is

CONTRACTOR TO PERFORM SELF INSPECTION ON ALL SEDIMENT AND EROSION CONTROL MEASURES AFTER EACH PHASE OF CONSTRUCTION TO ENSURE THE EROSION CONTROL & SEDIMENTATION PLANS ARE BEING FOLLOWED. COMPLETE THE SELF-INSPECTION REPORT (OBTAIN FROM NCDENR WEBSITE) AND PROVIDE TO OWNER AND ENGINEER.

roject Number: 2025-104 DWG Name: 2025-104 details.dwg

Drawing Scale: as noted

Date of Project: 8-1-2025 Christopher L. Price, P.E.

South Carolina PE# 22396 Indiana PE # 12100391

Certificates of Authorization SC C04212 - GA PEF005865 NC P0868 - AL CA4065E

Z

Munster

O

age

tor


elf


S




SITEWORK NOTES &

DETAILS








CONSTRUCTION PROGRESSES. B. WASHOUT MUST BE CLEANED OR NEW FACILITIES 6. AT LEAST WEEKLY REMOVE ACCUMULATION OF CONSTRUCTED AND READY TO USE ONCE SAND AND AGGREGATE AND DISPOSE OF PROPERLY

**CONCRETE WASHOUT AREA** 

WASHOUT IS 75% FULL.



1. CONTRACTION JOINTS 10' O/C

2. EXPANSION JOINTS 100' O/C 3. ALL JOINTS SEALED PER SCDOT SPECS. SURFACE SHALL


RECEIVE A MEDIUM BROOM FINISH. 4. THE SUBGRADE SHALL BE THOROUGHLY COMPACTED TO 95% OF THE STANDARD PROCTOR DENSITY AND FINISHED TO A SMOOTH, FIRM SURFACE AND SHALL BE MOIST AT

# 18" CONCRETE CURB & GUTTER

THE TIME THE CONCRETE IS PLACED.

- TYPICAL DETAIL - STANDARD -

NTS



NOTES:
1. CONTRACTION JOINTS 10' O/C

2. EXPANSION JOINTS 100' O/C


3. ALL JOINTS SEALED PER SCDOT SPECS. SURFACE SHALL RECEIVE A MEDIUM BROOM FINISH.


4. THE SUBGRADE SHALL BE THOROUGHLY COMPACTED TO 95% OF THE STANDARD PROCTOR DENSITY AND FINISHED TO A SMOOTH, FIRM SURFACE AND SHALL BE MOIST AT THE TIME THE CONCRETE IS PLACED.


# 18" CONCRETE CURB & GUTTER


- TYPICAL DETAIL - PITCHED -


NTS











SITEWORK NOTES & **DETAILS** 

DWG Name: 2025-104 details.dwg Drawing Scale: as noted Date of Project: 8-1-2025 Christopher L. Price, P.E. South Carolina PE# 22396 Indiana PE # 12100391

Certificates of Authorization SC C04212 - GA PEF005865

NC P0868 - AL CA4065E

**O** ğ


tor

S


STATE OF


2. 90° PARKING LAYOUT SHOWN. STRIPING ORIENTATION AND DIMENSIONS SIMILARLY SHALL APPLY TO ANGLED PARKING ALIGNMENT. ADA ACCESSIBILITY STRIPING


N.T.S.



ADA ACCESSIBILITY SYMBOL N.T.S.









NOTE
1. 12"x18" ACCESSIBILITY SIGN (R7-8) SHALL BE MOUNTED 7' FROM FINISH GRADE TO BOTTOM EDGE OF SIGN FACE.
MOUNTING HEIGHT MAY BE REDUCED TO 5' IF PLACED IN A LANDSCAPE AREA IN WHICH PEDESTRIANS ARE NOT EXPECTED TO USE. BOLLARD MAY BE OMITTED IF INSTALLED IN LANDSCAPE AREAS. WHEN INSTALLED IN LANDSCAPE AREAS, MOUNTING POST SHALL BE DRIVEN A MINIMUM OF 3' BELOW FINISH GRADE. ALTERNATE MOUNTING POSTS MUST BE APPROVED BY THE CITY ENGINEER PRIOR TO CONSTRUCTION. 5. ALL SIGNAGE SHALL BE ENGINEER GRADE .080 ALUMINUM REFLECTIVE SIGN MEETING THE REQUIREMENTS OF THE MUTCD AND ADAAG.


> ADA ACCESSIBILITY SIGN N.T.S.



## LIGHT DUTY ASPHALT PAVEMENT




#### TYPICAL SECTION -HEAVY DUTY ASPHALT PAVEMENT



# TYPICAL SECTION -**HEAVY DUTY CONCRETE**

**PAVEMENT NOTE:** THE ABOVE PAVEMENT SECTIONS ARE TO BE APPROVED BY THE OWNER AND GEOTECHNICAL ENGINEER PRIOR TO INSTALLATION.





Project Number: 2025-104


Drawing Scale: as noted

Date of Project: 8-1-2025


DWG Name: 2025-104 details.dwg


Munster torage

Self




SITEWORK NOTES & **DETAILS** 






STORM DRAINAGE MANHOLE

STORM DRAINAGE BEDDING





CATCH BASIN - HOODED GRATE INLET CATCH BASIN - HOODED GRATE INLET


Project Number: 2025-104 DWG Name: 2025-104 details.dwg Drawing Scale: as noted Date of Project: 8-1-2025 Christopher L. Price, P.E. South Carolina PE# 22396 Indiana PE # 12100391


Certificates of Authorization: SC C04212 - GA PEF005865 NC P0868 - AL CA4065E


torage

Self

SITEWORK NOTES & **DETAILS** 







Project Number: 2025-104

DWG Name: 2025-104 details.dwg

Drawing Scale: as noted

Date of Project: 8-1-2025

Engineer of Record:

Christopher L. Price, P.E.
South Carolina PE# 22396
Indiana PE # 12100391

| Carlotte | Carlotte

Certificates of Authorization: SC C04212 - GA PEF005865 NC P0868 - AL CA4065E

45th Street

torage

Self

No. 12100391

STATE OF


WOLANA

SITEWORK NOTES & DETAILS

C505


SANITARY SEWER CLEANOUT DETAIL

NOT TO SCALE



#### NOTES:


- 1) DIMENSIONS OF CONCRETE COLLARS BASED ON 2000 P.S.F. SOIL BEARING.
- 2) DIMENSIONS OF WELDED STEEL OR DUCTILE IRON THRUST COLLARS SHALL CONFORM TO THE PIPE MANUFACTURER'S SUPPLIED SHOP DRAWINGS WHICH SHALL INDICATE A THRUST RATING NOT LESS THAN THAT INCLUDED IN THE CHART BELOW.
- 3) CONCRETE SHALL HAVE A COMPRESSIVE STRENGTH OF 3,000 P.S.I. AT 28 DAYS. "HIGH EARLY" CONCRETE SHALL
- 4) SOIL CONDITIONS SHALL BE VERIFIED BY THE INSPECTOR PRIOR TO CONSTRUCTION.
- 5) FOR 3" PIPE USE 4" DIAMETER THRUST RATING.




PIPE SIZE	А	В	С	D	E	CY	WELDED THRUST COLLAR MINIMUM RATING
4"	3'-0"	2'-0"	1'-6"	1'-6"	9"	0.33	4,500 lbs
6"	4'-0"	2'-0"	1'-6"	2'-0"	9"	0.44	9,300 lbs
8"	4'-6"	2'-0"	2'-0"	2'-3"	1'-0"	0.67	16,000 lbs
12"	6'-0"	2'-0"	3'-0"	3'-0"	1'-6"	1.33	34,000 lbs
16"	6'-6"	2'-0"	4'-6"	3'-3"	2'-3"	2.17	59,000 lbs


## TYPICAL CONCRETE COLLAR DETAIL

N.T.S.



- 1. FIRE HYDRANTS SHALL NOT BE INSTALLED IN EXISTING OR PROPOSED SIDEWALKS
- 2. FIRE HYDRANTS SHALL BE INSTALLED PRIMED ONLY. THEY SHALL BE PAINTED AFTER INSTALLATION. 3. FIRE HYDRANTS SHALL BE COATED WITH 2 COATS BENJAMIN MOORE PAINT RUST INHIBITOR
- #16378 ALUMINUM OR EQUAL. 4. DOUBLE WRAP ALL D.I. FITTINGS WITH POLY WRAP INCLUDING BOLTS AND NUTS.
- 5. INSTALL RESTRAINED OFFSET BENDS OR "GRADELOCK" FITTINGS ON FIRE HYDRANT SUPPLY LINE SO FIRE HYDRANT BURY DEPTH IS NO GREATER THAN SIX FEET.
- 6. ALL FITTINGS SHALL INCORPORATE MEGALUG MECHANICAL JOINT RESTRAINTS OR APPROVED EQUAL.
- 7. SWIVEL SOLID ADAPTER ON CONCRETE CYLINDER PIPE FLANGED OUTLET.





PIPE	"x"										1
SIZE	DIM. IN. FT.	"A"	MIN. AREA	"B"	MIN. AREA	"C"	MIN. AREA	"D"	MIN. AREA	"E"	MIN. AREA
4"	1.5	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.06	1.00	1.00
6"	1.5	1.00	1.00	1.00	1.00	1.14	1.30	1.55	2.40	1.30	1.70
8"	1.5	1.00	1.00	1.08	1.18	1.52	2.31	2.07	4.27	1.74	3.02
10"	1.5	1.00	1.00	1.35	1.84	1.90	3.61	2.58	6.66	2.17	4.71
12"	1.5	1.00	1.33	1.63	2.65	1.86	5.19	3.10	9.60	2.61	6.79
14"	1.5	1.03	1.81	1.90	3.60	2.66	7.07	3.61	13.06	3.04	9.24
16"	2.0	1.18	2.36	2.17	4.71	3.04	9.23	4.13	17.06	3.47	12.06
18"	2.0	1.33	2.99	2.44	5.96	3.42	11.69	4.65	21.59	3.91	15.27
20"	2.0	1.48	3.70	2.71	7.35	3.80	14.43	5.16	26.66	4.34	18.85
21"	2.0	1.55	4.07	2.85	8.11	3.99	15.91	5.42	29.39	4.56	20.78
24"	2.0	1.77	5.32	3.25	10.59	4.56	20.77	6.20	38.39	5.21	27.14
27"	2.5	1.99	6.73	3.66	13.40	5.13	26.29	6.97	48.58	5.86	34.35
30"	2.5	2.22	8.31	4.07	16.55	5.70	32.46	7.74	59.98	6.51	42.41
33"	2.5	2.44	10.06	4.47	20.02	6.27	39.28	8.52	72.57	7.16	51.31
36"	2.5	2.66	11.97	4.88	23.83	6.84	46.74	9.29	86.37	7.81	61.07
39"	3.0	2.88	14.05	5.29	27.97	7.41	54.86	10.07	101.36	8.47	71.68
42"	3.0	3.10	16.30	5.69	32.43	7.98	63.62	10.85	117.56	9.12	83.13

NOTE: CLASS "B" CONCRETE 2,000 PSI SHALL BE USED FOR ALL BLOCKING UNLESS OTHERWISE NOTED ON STANDARD DETAILS AND / OR PLANS. THE MINIMUM VERTICAL DIMENSION OF ALL BLOCKING SHALL BE 1.5 TIMES
THE PIPE DIAMETER WITH AT LEAST 0.75 TIMES THE PIPE DIAMETER EXTENDING
BOTH ABOVE AND BELOW THE PIPE CENTERLINE. THIS DIMENSION DETERMINES THE "A" DIMENSION FOR 11-1/4° BENDS.

FOR 22-1/2°, 45°, 90°, AND TEES AND PLUGS, THE VERTICAL DIMENSION SHALL BE EQUAL TO THE HORIZONTAL DIMENSION SHOWN TO PRODUCE THE REQUIRED MINIMUM AREA.

ALL MINIMUM AREAS ARE IN SQUARE FEET. BLOCKING TO BE AGAINST UNDISTURBED TRENCH WALLS AND BOTTOM. DOUBLE WRAP ALL D.I. FITTINGS INCLUDING BOLTS AND NUTS WITH POLY WRAP AND TAPE IN PLACE.

#### DESIGN DATA:

SOIL CONDITIONS SHALL BE VERIFIED BY THE

INSPECTOR BEFORE DESIGN IS IMPLEMENTED.

SECTION A-A

@ DIMENSIONS OF THRUST BLOCK IN FEET BASED ON 2000 POUNDS PER SQUARE FOOT SOIL BEARING PRESSURE AND 200 POUNDS PER SQUARE INCH TEST PRESSURE. ACTUAL INSIDE DIAMETER OF DUCTILE IRON PIPE, CLASS 51 USED AS STANDARD.

© CONCRETE SHALL HAVE A COMPRESSIVE STRENGTH OF 3000 P.S.I.

AT 28 DAYS. HIGH EARLY CONCRETE SHALL BE USED.

#### MINIMUM DIMENSIONS FOR CONCRETE BLOCKING

VOLUME CY 11 1/4° 22 1/2° 1.33 0.44 3.15 90° TEES, PLUGS TS & V

TYPICAL HORIZONTAL THRUST BLOCK

FOR 3" & 4" USE 6" SIZES

SITEWORK NOTES & N.T.S. DETAILS

DWG Name: 2025-104 details.dwg Drawing Scale: as noted Date of Project: 8-1-2025 Christopher L. Price, P.E. South Carolina PE# 22396 Indiana PE # 12100391

Project Number: 2025-104


- FRONT VIEW Certificates of Authorization SC C04212 - GA PEF005865 NC P0868 - AL CA4065E


age

tor

S

No. 12100391 STATE OF





Christobher T. Bill Complement of the String South Carolina Definition of the String South Carolina Definition of the String String South Carolina Definition of the S

Project Number: 2025-104

Drawing Scale: as noted

Date of Project: 8-1-2025

DWG Name: 2025-104 details.dwg

torage Munster IN
----

Certificates of Authorization: SC C04212 - GA PEF005865

NC P0868 - AL CA4065E



LAN /ISION	ISSUE DATE	ISSUE COMMENT
Α	8-7-2025	ISSUED FOR REVIEW
В	9-16-2025	ISSUED FOR PERMIT

SITEWORK NOTES & DETAILS

C507