

ESTIMATE

Oak Ridge Fence and Gate Inc.
3045 Louis Sherman Dr
Steger, IL 60475

Calumet pump
julie@oakridgefence.net
+1 (708) 357-4105
oakridgefence.net



Bill to

TOWN OF MUNSTER PUBLIC WORKS
508 FISHER STREET
MUNSTER, IN 46321 US

Ship to

TOWN OF MUNSTER PUBLIC WORKS
508 FISHER STREET
MUNSTER, IN 46321 US

Estimate details

Estimate no.: 2175168
Estimate date: 04/16/2025
Expiration date: 05/15/2025

#	Date	Product or service	Description	Qty	Rate	Amount
1.		Ameristar Montage Plus	FURNISH AND INSTALL 62' OF AMERISTAR MONTAGE PLUS STYLE: CLASSIC HEIGHT: SIX FOOT COLOR: BLACK 3" X 12GA X 96" END AND CORNER POSTS 4" X 11GA X 96" GATE POSTS (1) 12' WIDE DOUBLE GATE AND HARDWARE ALL POSTS SET IN CONCRETE FOOTINGS SPECIAL ORDER, NON- RETURNABLE. 5 WEEK LEAD TIME	1	\$14,700.00	\$14,700.00
2.		INDUSTRIAL CHAIN LINK FENCE	FURNISH AND INSTALL APPROXIMATELY 280' OF 2 X 8 X 72" + B/W BLACK CHAIN LINK FENCE SYSTEM 280' OF BLACK BOTTOM LOCK PDS 3" X 10' 6" END AND CORNER POSTS 2 1/2" X 9' LINE POSTS (1) EVERY 8' OR LESS ALL POSTS SET IN CONCRETE FOOTINGS	1	\$16,450.00	\$16,450.00

Total

\$31,150.00

Deposit
due

\$10,000.00