

L2 Incorporated
901 E Summit St. Suite C. Crown Point, IN
Phone:219-577-6672



PROPOSAL # 0630202511

6/30/2025

BILL TO	PROJECT ADDRESS	PROJECT NAME
Town Of Munster	8713 Crestwood Dr	Sewer Repair
1005 Ridge Rd	Munster, IN	Bob V
Munster, IN 46321		

DESCRIPTION

Supply Labor, Equipment, and Material for the following:

-Excavate trench to expose 14 lineal feet of shifted sewer pipe

-Remove up to 14 lineal feet of damaged sewer pipe

-Supply and install new up to 14' x 15" SDR 35 sewer pipe

Fill around new sewer pipe with 8's stone

-Back fill remaining trench with previously excavated materials

-Truck remaining excavated materials offsite

-No grass seed included in this proposal

-Scope includes for 15" sewer pipe. If pipe diameter greater than 15", L2 Incorporated to present material price difference

-Others to remove existing trees

DESCRIPTION

Requirements to execute this proposal:

- Consecutive day access Monday-Friday ~7am-3:30pm, week after week until completion
- 360 degree access around foundations/slabs/columns with no operations interruptions
- Proposal pricing valid for 15 days

This proposal does not include:

- No de-watering, no OT hours, no blankets, no permitting, no surveying/engineering
- No responsibility for subgrade compaction/conditions
- No winterization for existing ground conditions, blankets, or concrete winterization additives
- No mechanical components for labor or material
- No scope included for unforeseen underground infrastructure I.E. (sewer, water, gas, pre-existing foundations etc)

Proposal Valid for 15 days

Separate proposals to be provided for unforeseen items not described in this proposal

PROPOSAL TOTAL:	\$39,470.28
DUE BEFORE PROJECT START DATE	\$11,835.63
DUE UPON COMPLETION OF THIS PROPOSAL	\$27,634.65
L2 INCORPORATED TO PRORATE PAYMENT AMOUNT AND TERMS DUE TO UNFORSEEN DELAYS MATERIAL, WEATHER, OR CLIENT CHANGED SCHEDULING RELATED ITEMS	

Thank you for your business!