Copyright 2022 Albert E. Berg III ltd. Is sole owner and reserves the right to these plans and the ideas expressed therein. They (Plans) may not be reproduced or copied in any form or assigned to a third party without the written permission from Albert E. Berg III ltd. (Designs by AEB III ltd.) Plans are a (1) ONE time build, if used to build a second time a fee of $1000 shall be assessed each time used.



LEFT SIDE ELEVATION SCALE: 1/8"=1'-0"

Design Loads:	Live Load:	Dead Load:
Living area:	40PSF	10PSF
Sleeping area:	30PSF	10PSF
Ceiling Joists:	20PSF	10PSF
(no storage above)		
Roof area:	30PSF	15PSF



RIGHT SIDE ELEVATION SCALE: 1/8"=1'-0"

GENERAL ELEVATION NOTES:

1. CONTRACTOR NOTE:
   ALL TRADES MUST CONFORM TO CURRENT EXISTING CODES APPLYING TO THIS PROJECT. CONTRACTORS TO VERIFY ALL DIMENSIONS AND CONDITIONS BEFORE EXECUTING ANY WORK. REPORT ANY DISCREPANCIES AT ONCE. DO NOT SCALE DRAWINGS. USE FIGURED DIMENSIONS ONLY.
2. ✳ ALL BEDROOMS SHALL HAVE AT LEAST ONE "EGRESS WINDOW" SEE "BOCA" SPECIFICATIONS.
3. ⊗ UNIT GLASS AND/OR MULTIPLE UNIT GLASS SHALL BE INSULATED TEMPERED SAFETY GLASS PER ANSI's SPECS.
4. WINDOW AND PATIO DOOR DESIGNATIONS INDICATES ANDERSEN MANUFACTURED CLAD WINDOWS. COORDINATE WINDOW AND DOOR MANUFACTURER WITH OWNER FOR EXACT SIZES AND TYPES.
5. PROVIDE SPLASH BLOCKS AT ALL DOWNSPOUTS.
   PROVIDE DRIP CAPS AT ALL WINDOWS, DOORS AND RAKES.
   WRAP EAVE RETURNS WITH RAIN GUTTER AND FLASH AS NOTED.
6. FIREPLACE FLUES TO BE MIN. (2'-0") ABOVE ANY ROOF SURFACE WITHIN MIN. HORIZONTAL DISTANCE OF (10'-0")
7. ALL BRICK WORK SHALL BE TYPICAL BRICK VENEER UNLESS NOTED OTHERWISE.
8. ALL SOLDIER AND ROWLOCK BRICK COURSE SHALL PROJECT 3/4" FROM FACE OF VENEER UNLESS NOTED OTHERWISE.



PROPOSED FRONT ELEVATION SCALE: 1/4"=1'-0"

While every attempt has been made in the preparation of this plan to avoid mistakes, this firm can not guarantee against human error. The contractor and Owner shall check all Dimensions, Details and Jobsite conditions and be responsible for them. Written dimensions on the drawings take precedence over scaled dimensions. Designs by AEB III ltd., (A. E. Berg) shall not be held responsible for construction methods or means by the Contractor, Sub-contractors and there Tradesmen and/ or Owner.

REVISIONS	BY
FINAL-22	AB

CARBONARE ENTERPRISES LLC
Louis Carbonare - Owner
LouisCarbonare@gmail.com 219.776.3902

PROPOSED NEW RESIDENCE
Educate Residence
8120 Castle Drive
Munster, Indiana 46321

Designs by AEB III ltd,
8205 Parkview Avenue
Munster, Indiana 46321
708-890-7209
Aebdesigns3@gmail.com

AEB

Date 02.22.2022
Scale AS NOTED
Drawn AB
Job 021-015-LC
Sheet A-1
Of 7 Sheets



PROPOSED SITE PLAN SCALE: 1" = 20'

GENERAL ELEVATION NOTES

1. CONTRACTOR NOTE:
   ALL TRADES MUST CONFORM TO CURRENT EXISTING CODES APPLYING TO THIS PROJECT. CONTRACTORS TO VERIFY ALL DIMENSIONS AND CONDITIONS BEFORE EXECUTING ANY WORK. REPORT ANY DISCREPANCIES AT ONCE. DO NOT SCALE DRAWINGS. USE FIGURED DIMENSIONS ONLY.
2. ✳ ALL BEDROOMS SHALL HAVE AT LEAST ONE "EGRESS WINDOW" SEE "BOCA" SPECIFICATIONS.
3. ⊕ UNIT GLASS AND/OR MULTIPLE UNIT GLASS SHALL BE INSULATED TEMPERED SAFETY GLASS PER ANSI's SPECS.
4. WINDOW AND PATIO DOOR DESIGNATIONS INDICATES ANDERSEN MANUFACTURED CLAD WINDOWS. COORDINATE WINDOW AND DOOR MANUFACTURER WITH OWNER FOR EXACT SIZES AND TYPES.
5. PROVIDE SPLASH BLOCKS AT ALL DOWNSPOUTS. PROVIDE DRIP CAPS AT ALL WINDOWS, DOORS AND RAKES. WRAP EAVE RETURNS WITH RAIN GUTTER, AND FLASH AS NOTED.
6. FIREPLACE FLUES TO BE MIN. (2'-0") ABOVE ANY ROOF SURFACE WITHIN MIN. HORIZONTAL DISTANCE OF (10'-0")
7. ALL BRICK WORK SHALL BE TYPICAL BRICK VENEER, UNLESS NOTED OTHERWISE.
8. ALL SOLDIER AND ROWLOCK BRICK COURSE SHALL PROJECT 3/4" FROM FACE OF VENEER UNLESS NOTED OTHERWISE.

LIGHT + VENTILATION SCHEDULE

ROOM	FL.	LIGHT 8%		VENT 4%		MECH.
		REQ	ACT.	REQ	ACT	
GREAT ROOM	616SF	49.2	140.0	24.6	120.0	
KITCHEN	308SF	24.6	26.2	12.3	26.2	
DINING	140SF	11.2	91.7	5.6	88.2	
OFFICE	143SF	11.4	52.4	5.7	50.4	
SUITE 1	240SF	19.2	85.5	9.6	83.0	
BED 2	182SF	14.5	52.4	7.2	50.4	
BED 3	192SF	15.3	39.3	7.6	37.8	
BED 4	210SF	16.8	85.5	8.4	83.0	
POWDER RM	30SF	ARTIFICAL				75CFM
BATH 1	90SF					150CFM
BATH 2	30SF					75CFM
BATH 4	112SF					150CFM
BATH 5	45SF					75CFM
LAUNDRY	75SF					75CFM
BASEMENT	2%	ARTIFICAL				

STEEL LINTELS FOR MASONRY

CLEAR SPAN(MAX)	EXTERIOR ANGLES	INTERIOR ANGLES
4'-0"	L 3 1/2" x 3 1/2" x 5/16"	2 L's 3 1/2" x 3 1/2" x 5/16"
6'-0"	L 4" x 3 1/2" x 5/16"	2 L's 4" x 3 1/2" x 5/16"
8'-0"	L 5" x 3 1/2" x 5/16"	2 L's 5" x 3 1/2" x 5/16"

Design Loads:	Live Load:	Dead Load:
Living area:	40PSF	10PSF
Sleeping area:	30PSF	10PSF
Ceiling Joists: (no storage above)	20PSF	10PSF
Roof area:	30PSF	15PSF



REAR ELEVATION SCALE: 1/4" = 1'-0"

While every attempt has been made in the preparation of this plan to avoid mistakes, this firm can not guarantee against human error. The contractor and Owner shall check all Dimensions, Details and Jobsite conditions and be responsible for them. Written dimensions on the drawings take precedence over scaled dimensions. Designs by AEB III ltd,. (A. E. Berg) shall not be held responsible for construction methods or means by the Contractor, Subcontractors and there Tradesmen and/ or Owner.

REVISIONS	BY
FINAL.22	AB

CARBONARE ENTERPRISES LLC
Louis Carbonare - Owner
LouisCarbonare@gmail.com
219.776.3902

PROPOSED NEW RESIDENCE
Educate Residence
8120 Castle Drive
Munster, Indiana 46321

Designs by AEB III ltd,
8205 Parkview Avenue
Munster, Indiana 46321
708-890-7209
Aebdesigns3@gmail.com

Date	02.22.2022
Scale	AS NOTED
Drawn	AB
Job	021-015-LC
Sheet	A-2
Of	7 Sheets

Copyright 2022 Albert E. Berg III ltd. Is sole owner and reserves the right to these plans and the ideas expressed therein. They (Plans) may not be reproduced or copied in any form or assigned to a third party without the written permission from Albert E. Berg III ltd. (Designs by AEB III ltd.) Plans are a (1) ONE time build, if used to build a second time a fee of $1000 shall be assessed each time used.

24 X 36 CLEARPRINT


116'-0"
22'-0"
41'-8"
94'-2"
13'-4"
1'-2"
12'-8"
1'-2"
13'-4"
27'-8"
24'-10"
32'-6"
71'-8"
23'-8"
15'-6"
15'-5"
15'-5"
10"
7'-0"
8"
CRAWL SPACE
2" MUD SLAB W/FIBER REINF. OVER .06 MIL. V.B. OVER 4" GRANULAR FILL COMP. 95% MIN.
3½"Ø CONC. FILLED STL. COLUMN. 3'-0"x 3'-0"x 14"D. CONC. PAD W/3-#4 REBAR EACH WAY
W10x26
2x12" FLOOR JOISTS @16"O.C. #2SPF
DBL 2"x12" FLOOR JOISTS @16"O.C. #2SPF
2"x12" FLOOR JOISTS @16"O.C. #2SPF
C A-4
6" STAIR STOOP ARMS
UNEXCAVATED
5" CONCRETE SLAB W/1.9x1.9 WWF OVER 6" MIN. GRANULAR FILL COMP. 95% MIN. (TYP.)
ACCESS FOR DUCT WORK SEE HVAC CONTRACTOR
* PROVIDE RADON GAS SYSTEM PER CODE
C.I. WELL W/C.I. COVER + 4"Ø DRAIN + LATTER
CW4145 R.O. 3'-0½"x4'-5⅜"
SET COVER FLUSH W/ T/C SLAB
DROP T/C 10"
2'-8"
2'-4"
4'-6"
10'-0"
14'-6"
WH
F.
ALL MECH. EQUIPMENT SHALL HAVE MANF. SPECS. ATTACHED @TIME OF INSPECTION
2PCS 1¾"x11⅞" MICRO-LAM IN CONT.
FD.
16'-0"
8"
SHORT COLUMNS
BASEMENT
4" CONCRETE SLAB W/1.9x1.9 WWF. OVER .06 MIL. V.B. OVER 6" GRANULAR FILL COMPACTED 95% MIN.
11'-0"
16'-0"
DBL 2"x12" FLOOR JSTS @16"O.C. #2SPF
DBL JSTS
3½"
6'-8"
3⁰6⁸ 1HR
WPW 3056 -2 R.O. 3'-2⅛"x5'-8⅞"
3⁰6⁸
2-50GAL. WH IN TANDUM W/ RECIRCULATOR
3½"Ø CONC. FILLED STL. COLUMN. 3'-0"x 3'-0"x 14"D. CONC. PAD W/3-#4 REBAR EACH WAY (TYP.)
ROUGH-IN FOR FUTURE BATH
FUTURE STUD WALLS
2"x4" STUDS @ 16" O.C. TREATED BTM. PLATE W/⅝" S.R.
2PCS 1¾"x11⅞" MICRO-LAM
1'-6"
SP.
DW.
R
14'-10"
DRAIN TILE SHALL BE COVERED W/APPROVED FIBER MEMBRAIN. TILE SHALL BE PLACED ON MIN. 2" GRAVEL BASE CONTAINING NO MORE THAN 10% MAT'L. THAT PASSES THRU A #4 SIEVE. COVER W/6" SAME MAT'L.
3'-0"W x 2'-0"D ACCESS TO CRAWL
DROP T/C WALL 2'-6"
UNEXCAVATED
5" CONC. SLAB W/1.9x1.9 WWF OVER 6" MIN. GRANULAR FILL COMP. 95% MIN.
UNEXCAVATED
10'-8"
4'-2"
DROP T/C 10"
3'-8"
9'-2"
11'-8"
5'-0"
E.J.
FD.
8'-10"
8'-2"
11'-2"
13'-0"
2-#5 REBAR @ 2'-0" O.C. @ TOP
A A-4
B A-4
FINISHED BASEMENT
4" CONCRETE SLAB W/ 1.9x1.9 WWF OVER .06 MIL. V.B. OVER GRANULAR FILL COMP. 95% MIN. (TYP.)
2⁸6⁸ 1HR
UP
4'-0"
3½"Ø CONC. FILLED STL. COLUMN. 3'-0"x3'-0"x14"D CONC. PAD. W/3-#4 REBAR EACH WAY (TYPICAL).
2"x4" STUDS @ 16" O.C. TREATED BTM. PLATE ⅝" FC. SHEETROCK ON CEILING + WALLS
* SEE PLUMBER FOR SPEC. ON FLOOR WATER HEAT
W.H.
TO GARAGE FLOOR
ELEV. PIT
4" CONC. SLAB W/ 1.9x1.9 WWF. W/ .06 MIL. V.B. W/ 6" GRANULAR FILL COMP. 95% MIN.
8" CONCRETE FDN. WALL W/2 #4 REBAR TOP + BTM. CONTINUOUS
THICKEN SLAB 2'-0"x 14"D. UNDER WALLS
8'-8"
CHECK WITH OWNER FOR ACTUAL UNIT SELECTED *
UNEXCAVATED
4" CONCRETE SLAB W/1.9x1.9 WWF. OVER .06 MIL. VAPOR BARRIOR OVER 6" COMPACTED GRANULAR FILL 95% MIN.
12'-4"
4'-4"
55'-8"
39'-0"
24'-0"
DROP T/C 12" POUR SLAB THRU
5'-2"
8'-0"
3'-0"
10'-3"
1'-8"
3'-6"
2'-0"
66'-6"
2'-0"
10'-3"
10'-3"
3'-0"
8"
2'-0"
10'-3"
15'-10"
11'-0"
16'-6"
6" 2'-0" 6"
9'-8"
15'-2"
12'-8"
3'-0"
10'-6"
3'-0"
12'-8"
15'-2"
3'-2"
6'-2"
11'-8"
6'-2"
24'-0"
B A-4
A A-4

While every attempt has been made in the preparation of this plan to avoid mistakes, this firm can not guarantee against human error. The contractor and Owner shall check all Dimensions, Details and Jobsite conditions and be responsible for them. Written dimensions on the drawings take precedence over scaled dimensions. Designs by AEB III ltd,. (A. E. Berg) shall not be held responsible for construction methods or means by the Contractor, Sub-contractors and there Tradesmen and/ or Owner.

PROPOSED BASEMENT PLAN

SCALE: 1/4"=1'-0"

REVISIONS	BY
FINAL. 22	AB

CARBONARE ENTERPRISES LLC
Louis Carbonare - Owner
LouisCarbonare@gmail.com 219.776.3902

PROPOSED NEW RESIDENCE

Educate Residence
8120 Castle Drive
Munster, Indiana 4632

Designs by AEB III ltd,
8205 Parkview Avenue
Munster, Indiana 46321
708-890-7209
Aebdesigns3@gmail.com

Date 02-22-2022
Scale AS NOTED
Drawn AB
Job 021-015-LC
Sheet A-3
Of 7 Sheets

MAIN: 4018 SF
PORCH: 885 SF
GARAGE: 1460 SF
TOTAL: 6689 SF

PORTICAL: 266 SF

While every attempt has been made in the preparation of this plan to avoid mistakes, this firm can not guarantee against human error. The contractor and Owner shall check all Dimensions, Details and Jobsite conditions and be responsible for them. Written dimensions on the drawings take precedence over scaled dimensions. Designs by AEB III ltd, (A.E. Berg) shall not be held responsible for construction methods or means by the Contractor, Sub-contractors and there Tradesmen and/ or Owner.



PROPOSED FLOOR PLAN

SCALE: 1/4"=1'-0"

REVISIONS	BY
REVISED 12-8	BB
FINAL-22	AB

Designs by AEB III ltd,
8205 Parkview Avenue
Munster, Indiana 46321
708-890-7209
Aebdesigns3@gmail.com

PROPOSED NEW RESIDENCE
Educate Residence
8120 Castle Drive
Munster, Indiana 4632

CARBONARE ENTERPRISES LLC
Louis Carbonare - Owner
LouisCarbonare@gmail.com
219.776.3902

Date 02-22-2022
Scale AS NOTED
Drawn AB
Job 021-015-16
Sheet A-4
Of 7 Sheets

24 X 36
CLEARPRINT®

Roof area:	30PSF	15PSF
Design Loads:	Live Load:	Dead Load:
Living area:	40PSF	10PSF
Sleeping area:	30PSF	10PSF
Ceiling Joists:	20PSF	10PSF
(no storage above)		
Roof area:	30PSF	15PSF

GENERAL FOUNDATION NOTES

1. OWNER SHALL BE RESPONSIBLE TO HIRE A CERTIFIED TESTING LAB TO ASCERTAIN EXISTING SOIL CONDITIONS AND BEARING CAPACITY, CONTRACTORS SHALL MODIFY FOOTING AND FOUNDATION IF REQUIRED PER CERTIFIED SOIL REPORT. MINIMUM ALLOWABLE SOIL PRESSURE TO BE 3,000 PSF.
2. BACKFILL TO BE SAND OR STONE (WHICH DOES NOT CONTAIN ORGANIC MATTER, CONSTRUCTION DEBRIS AND LARGE ROCKS) INSTALLED IN LIFTS AND COMPACTED AS TO NOT DAMAGE WATERPROOFING.
3. PROVIDE MINIMUM 2% NATURAL VENTILATION FOR BASEMENT REQUIREMENT, SHALL BE AS WINDOWS AND/OR MECHANICAL MEANS.
4. FOOTING DRAIN TILE OPENING SHALL BE COVERED WITH APPROVED FILTER MEMBRANE DRAIN TILE SHALL BE PLACED ON NOT LESS THAN 2" GRAVEL OR CRUSHED STONE CONTAINING NOT MORE 10% MAT'L THAT PASSES THRU #4 SLEEVE AND SHALL BE COVERED WITH MIN. 12" OF SAME MATERIAL.
5. CONTRACTOR NOTE: ALL TRADES MUST CONFORM TO CURRENT EXISTING CODES APPLYING TO THIS PROJECT. CONTRACTORS TO VERIFY ALL DIMENSIONS AND CONDITIONS BEFORE EXECUTING ANY WORK. REPORT ANY DISCREPANCIES AT ONCE. DO NOT SCALE DRAWINGS. USE FIGURED DIMENSIONS ONLY.
6. CARPENTER CONTRACTOR TO VERIFY WITH CONTRACTOR IF JOIST SPACING IS TO BE CHANGED TO 12" O.C. UNDER CERAMIC TILE FLOOR AREAS.
7. CARPENTER CONTRACTOR TO VERIFY WITH CONTRACTOR IF JOIST SPACING IS TO BE CHANGED TO 12" O.C. UNDER TUB AREAS.
8. IF CONCRETE FLOOR, JOISTS & STEEL FOR FIRST FLOOR IS NOT IN PLACE FDN. WALLS SHALL BE BRACED WITH 2"x8" @ 45° TO TOP OF FOUNDATION WALLS 8'-0" O.C. AND AT ALL FOUNDATION CORNERS ±2'-0" FROM WALLS.


TYPICAL ROOF:
30 YR. ASPHALT SHINGLES OVER 15# ROOFING FELT W/ 2'-0" ICE + WATER SHIELD @ EAVES + VALLEYS OVER 7/16" O.S.B. SHEATHING OVER 2"x12" RAFTERS @ 16" O.C. #2SPF
1½" AIR GAP
5
12
TYPE 'K' ALUM. GUTTER + D. SPOUT
R.38 INSULATION
2"x10" CEILING JOISTS @ 16" O.C. #2SPF
½" SHEET ROCK
2-2"x6" TOP PLATE
R.19 MIN. INSULATION
ALUM. SOFFIT AND FASCIA W/CONTINOUS SCREEN
9'-0"
12'-0"
TYPICAL WALL:
BRICK VENEER W/ METAL TIES @ 32" O.C. HORZ. + 16" O.C. VERTICAL
1" AIR SPACE
HOUSE WRAP TAPED @ SEAMS
½" PLYWOOD SHEATHING
2"x6" STUDS @ 16" O.C.
R.19 MIN. INSULATION
½" SHEETROCK
WEEP HOLES @ 24" O.C.
TYPICAL FLOOR:
3/4" T+G PLYWOOD SUB FLOOR GLUED + SCREWED TO 2"x12" FLOOR JOISTS @ 16" O.C. #2SPF
R.19 INSULATION @ RIM JOIST
FLASHING
GRADE
8"
SOUND BATT INSULATION @ FINISHED BASEMENT
10" CONC. WALL
WALL BLANKET INSUL. R.11 MIN.
2"x6" TREATED SILL W/ SILL SEALER
½"Ø x 14" A.B. @ 6'-0" O.C. 2 BOLTS PER PLATE MAX. 1'-0" FROM CORNERS
10"
9'-0"
DAMPROOFING
TYPICAL BASEMENT SLAB:
4" CONCRETE SLAB W/ 1.9 x 1.9 W.W.F. OVER .06 MIL VAPOR BARRIOR OVER 4" MIN. GRANULAR FILL COMPACTED 95% MIN.
4"Ø DRAIN TILE W/APPROVED MEMBRAIN COVER W/ 12" WASHED GRAVEL 2" BELOW + 6" ABOVE
#5 REBAR TOP + BTM. CONT.
4"
10"
2-#5 REBAR CONT.
UNDISTURBED SOIL
1'-8"

TYPICAL WALL SECTION 'A' SCALE: ½" = 1'-0"



SECTION 'B' @ FIRE DOOR N.T.S.

* SEE MANUFACTORS SPEC'S FOR SIZING + DETAILS


5" STAMPED CONCRETE SLAB W/ 1.9x1.9 W.W.F. THICKEN @ EDGE
TROWL FACE OF CONCRETE SMOOTH. RADIUS TOP EDGE
GRADE VAIRES
6" MIN. COMPACTED FILL 95% MIN
8"
8" CONC. WALL
3'-6" MIN.
CONC. FDN. W/2 #5 REBAR
UNDISTURBED SOIL
1'-6"

SECTION 'C' SCALE: ½" = 1'-0"

While every attempt has been made in the preparation of this plan to avoid mistakes, this firm can not guarantee against human error. The contractor and Owner shall check all Dimensions, Details and Jobsite conditions and be responsible for them. Written dimensions on the drawings take precedence over scaled dimensions. Designs by AEB III ltd,. (A. E. Berg) shall not be held responsible for construction methods or means by the Contractor, Sub-contractors and there Tradesmen and/ or Owner.


RIDGE
RAFTERS PER PLAN
2"x4" STUDS @ 16" O.C. W/ R.19 INSUL AIR STOP
2PCS TREATED 2"x12" GLUED + BOLTED TOGETHER
3PCS TREATED 1¾" x 11⅞" MICRO LAM BOLTED TO HEADER
2"x10" CEILING JOISTS @ 16" O.C. W/ R.38 INSUL.
½" SHEETROCK
ALUM. SOFFIT + FASCIA (TYP.)
3PCS 2"x12" HEADER
BRICK VENEER
CUT STONE BRICK VENEER
CUT STONE BRICK VENEER
6"x6" TREATED POST
GLAS SIDE LITE (TEMPERED)
12'-0"
2"x TREATED FRAMING
6"x6" TREATED POST
3/4" T+G PLYWOOD SUB FLOOR GLUED + SCREWED TO 2"x12" FLOOR JOISTS W/ R.38 INSUL @ RIM JOIST
CONCRETE STEPS
½"Ø x 14" A.B. @ POST
5"
5"
CONC. PIER
5" CONC. DRIVE W/ 1.9x1.9 WWF OVER 6" COMPACTED GRANULAR FILL
5" CONC. PORCH W/ 1.9x1.9 WWF. THICKEN @ EDGE
TREATED 2"x6" SILL W/ SILL SEAL
½"Ø x 14" A.B. @ 6'-0" O.C. MIN. 2 PER PLATE
3'-6"
MIN. 2'-8"
10"
3-#5 REBAR EACH WAY
10"
R.19 WALL INSULATION
UNDISTURBED SOIL
4'-0"
DAMPROOFING
#4 REBAR CONTINOUS
4" CONCRETE SLAB W/ 1.9x1.9 WWF OVER .06 MIL. V.B. OVER 6" GRANULAR FILL COMP. 95%
2-#4 REBAR CONT.
UNDISTURBED SOIL
4"Ø DRAIN TILE W/APPROVED FIBER MEMBRAIN. TILE SHAL BE PLACED ON 2" MIN. GRAVEL + COVERED W/ 6" MIN. GRAVEL.

SECTION 'D' SCALE: ½" = 1'-0"

Copyright 2022 Albert E. Berg III ltd. Is sole owner and reserves the right to these plans and the ideas expressed therein. They (Plans) may not be reproduced or copied in any form or assigned to a third party without the written permission from Albert E. Berg III ltd. (Designs by AEB III ltd.) Plans are a (1) ONE time build, if used to build a second time a fee of $1000 shall be assessed each time used.

REVISIONS	BY
FINAL. 22	AB

CARBONARE ENTERPRISES LLC
Louis Carbonare - Owner
LouisCarbonare@gmail.com
219.776.3902

PROPOSED NEW RESIDENCE
Educate Residence
8120 Castle Drive
Munster, Indiana 46321

Designs by AEB III ltd,
8205 Parkview Avenue
Munster, Indiana 46321
708-890-7209
Aebdesigns3@gmail.com

Date 02.22.2022
Scale AS NOTED
Drawn AJ
Job 021.015.16
Sheet A.5
Of 7 Sheets



ELECTRICAL SYMBOL SCHEDULE

	SINGLE POLE WALL SWITCH [CENTER 48" AFF.]
	THREE-WAY WALL SWITCH [CENTER 48" AFF.]
	FOUR-WAY WALL SWITCH [CENTER 48" AFF.]
	DIMMER SWITCH [CENTER 48" AFF.]
	SINGLE POLE WALL SWITCH W/RED PILOT LIGHT [CENTER 48" AFF.]
	DUPLEX RECEPTACLE [CENTER 12" AFF.]
	DUPLEX RECEPTACLE SAME AS ABOVE EXCEPT SPLIT WIRED
	GROUND FAULT INTERRUPT DUPLEX RECEPTACLE [GFI] [WP]
	APPLIANCE OR EQUIPMENT RECEPTACLE
	SPECIAL OUTLET: TYPE AND USE AS NOTED
	SMOKE DETECTOR-110V, ALL INTERCONNECTED
	HEAT LAMP
	PORCELAIN PULL CHAIN FIXTURE
	CEILING-MOUNTED LIGHT FIXTURE
	RECESSED CAN LIGHT FIXTURE
	RECESSED ADJUSTABLE CAN LIGHT FIXTURE
#	RECESSED INCANDESCENT
	TELEVISION CONNECTION
	CEILING-MOUNTED PADDLE FAN W/O LIGHT
	GARAGE DOOR OPENER/LIGHT FIXTURE
□	SURFACE-MOUNTED FLUORESCENT LIGHT FIXTURE [4FT. OR 2FT.]
	EXHAUST FAN
	EXHAUST FAN & LIGHT
	EXTERIOR SOFFIT-MOUNTED LIGHT FIXTURE
	CORNER-MOUNTED MAKE-UP LIGHT
	WALL MOUNTED LIGHT
	EXTERIOR WALL-MOUNTED LIGHT FIXTURE
○	RECESSED PIN SPOT CAN LIGHT FIXTURE
	BATHROOM MIRROR LIGHT FIXTURE
	TELEPHONE

CONSULT PLANS FOR SYMBOLS PERTINENT TO THIS PROJECT.
NOT ALL SYMBOLS ARE USED IN ALL PROJECTS.

Electrical and HVAC locations are for representation only. Subjected to local codes and availability of materials.

PROPOSED MECH. PLAN

SCALE: ¼" = 1'-0"

While every attempt has been made in the preparation of this plan to avoid mistakes, this firm can not guarantee against human error. The contractor and Owner shall check all Dimensions, Details and Jobsite conditions and be responsible for them. Written dimensions on the drawings take precedence over scaled dimensions. Designs by AEB III ltd,. (A. E. Berg) shall not be held responsible for construction methods or means by the Contractor, Sub-contractors and there Tradesmen and/ or Owner.

MAIN: 4078 sf
PORCH: 885 sf
GARAGE: 1460 sf
TOTAL: 6689 sf

PORTICAL: 260 SF

REVISIONS	BY
REVISED 12-8	BQ
FINAL-22	AB

CARBONARE ENTERPRISES LLC

PROPOSED NEW RESIDENCE

Educate Residence

8120 Castle Drive
Munster, Indiana 4632

Designs by AEB III ltd,
8205 Parkview Avenue
Munster, Indiana 46321
708-890-7209
Aebdesigns3@gmail.com

Date 02.22.2022
Scale AS NOTED
Drawn AB
Job 021-015-LC
Sheet E-1
Of 7 Sheets

Copyright 2021 Albert E. Berg III ltd is sole owner and reserves the right to these plans and the ideas expressed therein.
They (plans) may not be reproduced or copied in any form or assigned to a third party without the written permission from
Albet E. Berg III ltd. ©.

Electrical and HVAC locations are for
representation only. Subjected to local
codes and availability of materials.



PROPOSED ELECTRIC PLAN SCALE: 1/4"=1'-0"

ENERGY COMPLIANCE NOTES:
- CERTIFICATE OF ALL INSULATION VALUES AND EQUIPMENT SIZES POSTED ON ELECTRICAL PANEL.
- WEATHER STRIPPED AND INSULATED ATTIC ACCESS PANEL.
- ALL DUCTS SEALED W/MASTIC OR UL 181 TAPE.
- AIR LEAKAGE: THE FOLLOWING MUST BE CAULKED, SEALED OR GASKETED.
  A) SITE-BUILT WINDOWS, DOORS AND SKY-LIGHTS.
  B) OPENINGS BETWEEN DOOR AND WINDOW ASSEMBLIES. (FIBERGLASS NOT PERMITTED)
  C) UTILITY PENETRATIONS.
  D) DROPPED CEILINGS OR CHASES ADJACENT TO THERMALK ENVELOPE.
  E) KNEE WALLS.
  F) WALLS AND CEILINGS SEPARATING A GARAGE FROM CONDITIONED SPACE.
  G) BEHIND TUBS AND SHOWERS ON EXTERIOR WALLS.
  H) COMMON WALLS BETWEEN DWELLING UNITS.
  I) ATTIC ACCESS OPENINGS.
  J) RIM JOIST JUNCTIONS.
  K) BOTTOM PLATES.
- BLOWER DOOR TESTING SHOWING LESS THAN 7 ACH @ 50 PA, OR 3RD PARTY VERIFIED INSPECTION CHECK-LIST COMPLETED. NOTE: TESTING REMOVES MAN EXPENSIVE CHECKLIST ITEMS. (SEE ATTACHED CHECKLIST)
- DUCT TESTING SHOWING LESS THAN 8 CFM PER 100 SQ FT REQUIRED IF ANY PORTION OF THE DUCT WORK IS OUTSIDE THE THERMAL BOUNDRY.

TYPICAL PERFORMANCE PATH MININUMS:
BASEMENT WALLS: R-10 4' DOWN
CRAWLSPACE WALLS: R-10 INTERIOR
SLABS: R-10 2' DOWN
RIM & BAND: R-13
EXTERIOR WALLS: R-13 & OSB.
CEILINGS: R-38 FLAT, R-30 VAULTED
WINDOWS: .35 U-FACTOR OR LOWER
DOORS: STANDARD INSULATED STEEL.

While every attempt has been made in the preparation of this plan to avoid mistakes, this firm can not guarantee against human error. The contractor and Owner shall check all Dimensions, Details and Jobsite conditions and be responsible for them. Written dimensions on the drawings take precedence over scaled dimensions. Designs by AEB III ltd,. (A. E. Berg) shall not be held responsible for construction methods or means by the Contractor, Sub-contractors and there Tradesmen and/ or Owner.

24 X 36 CLEARPRINT®

REVISIONS	BY
FINAL. 22	AB

CARBONARE ENTERPRISES LLC

PROPOSED NEW RESIDENCE
Educate Residence
8120 Castle Drive
Munster, Indiana 4632

Designs by AEB III ltd,
8205 Parkview Avenue
Munster, Indiana 46321
708-890-7209
Aebdesigns3@gmail.com

Date 02.22.2022
Scale AS NOTED
Drawn AB
Job 021-015-LC
Sheet E-2
Of 7 Sheets