

TO: President Gardiner and Members of the Town Council

FROM: Jill E. DiTommaso, PE

Deputy Town Manager

DATE: January 16, 2023

RE: Full-Service Water Tank Rehabilitation Maintenance Program

Background

There are seven water tanks in the Town's distribution system as listed below:

| Tank | Type | Capacity | Address | |
|-------------------------|--------------------|-----------------|-----------------------|--|
| Calumet East | Ground Storage | 400,000 gallons | 8103 Calumet Avenue | |
| Calumet West | Ground Storage | 400,000 gallons | 8103 Calumet Avenue | |
| White Oak/Fisher Street | Single Pedestal | 1 MG | 1631 Fisher Street | |
| Ridge Road | Double Ellipsoidal | 500,000 gallons | 1006 Ridge Road | |
| River Bend North | Ground Storage | 2 MG | 7800 River Bend Drive | |
| River Bend South | Ground Storage | 6.5 MG | 7800 River Bend Drive | |
| Superior Drive | Single Pedestal | 1 MG | 430 Superior Drive | |

These tanks are significant assets within the water system. A team of specialists is needed to inspect these assets and install and maintain the specialized coating systems that protect the tanks and keep them operational.

Methodology

In August 2022, the Town received two responses to a request for proposals to provide a maintenance service contract for the tanks. Proposers were asked to inspect the tanks and prepare a recommendation for repair, rehabilitation, and maintenance activities for all seven tanks in the distribution system.

Two proposals were received: one from Utility Service Company, Inc. (A Veolia Company) (Veolia) and one from SEH Design/Build, Inc. (SEH). Staff reviewed the proposals based on a number of criteria including price, project experience, and client references. Additional information was requested from Veolia to better compare the two proposals. Based on this analysis, staff recommends entering a 5-year maintenance contract with Veolia based on the scope of work outlined in the table on the next page.

This scope of work includes complete repainting of each tank within the next five years. Some tanks will be overcoated, while some will be completely sandblasted and repainted depending on the condition of the exterior coating system. The interior surfaces of each tank will be sandblasted and completely repainted. Yearly inspections will allow the Town to identify maintenance issues early to prevent costly repairs in the future.

Recommendation

By motion and voice vote authorize the Town Manager to sign the Master Services Agreement and seven Statement of Work contracts with Veolia for a full-service water tank rehabilitation maintenance program.

January 16, 2023 Full-Service Water Tank Rehabilitation Maintenance Program

Veolia Scope of Work

| Tank | SOW | 2023 | 2024 | 2025 | 2026 | 2027 | TOTAL |
|---------------------|-----|------------|------------|------------|------------|--------------|--------------|
| Calumet East* | 2 | \$ 142,844 | \$ 796 | \$ 825 | \$ 854 | \$ 2,652 | \$ 147,971 |
| Calumet West* | 1 | \$ 142,690 | \$ 796 | \$ 825 | \$ 854 | \$ 2,652 | \$ 147,817 |
| Ridge Road** | 3 | \$ 480,805 | \$ 796 | \$ 825 | \$ 854 | \$ 2,652 | \$ 485,932 |
| White Oak/Fisher** | 5 | \$ 769 | \$ 584,705 | \$ 825 | \$ 854 | \$ 3,536 | \$ 590,689 |
| River Bend North ** | 7 | \$ 769 | \$ 796 | \$ 608,693 | \$ 854 | \$ 884 | \$ 611,996 |
| Superior* | 4 | \$ 3,077 | \$ 796 | \$ 825 | \$ 333,504 | \$ 884 | \$ 339,086 |
| River Bend South** | 6 | \$ 769 | \$ 796 | \$ 825 | \$ 854 | \$ 1,424,210 | \$ 1,427,454 |
| TOTAL | | \$ 771,723 | \$ 589,481 | \$ 613,643 | \$ 338,628 | \$ 1,437,470 | \$ 3,750,945 |

Exterior overcoat
Exterior sandblast
Exterior/interior renovation and repairs
Washout inspection
Visual inspection